
**Chinese Listed Company Stock Code: SZ 300986** 



# GT18 Self Climbing Platform

(Intelligent Building Construction Protective Platform)



# **GETO Group**

#### **Headquarters:**

Greater Bay Area—No. 13 Heqing Road, Tsuihang New District, Zhongshan City, Guangdong Province

#### Southern China Production Base I:

Cuishan Lake Science and Technology Park, Kaiping, Jiangmen City, Guangdong Province

# Southern China Production Base II:

Huizhou Industrial Transfer Industrial Park, Huizhou City, Guangdong Province

# **Eastern China Production Base I:**

Guangchang Industrial Park, Fuzhou City, Jiangxi Province

# **Central China Production Base:**

Hi-tech Industry Development Zone, Xianning City, Hubei Province

#### **Northern China Production Base:**

China Aluminium Industrial Park, Lingu, Weifang City, Shandong Province

# **Southwest China Production Base:**

Modern Manufacturing Industrial Park, Tongnan High-Tech District, Chongqing City

#### **Northwest China Production Base:**

The Circular Economy Park, Anding District, Dingxi City, Gansu Province

# **Hainan Production Base:**

Gold Medal Port Industrial Park, Lingao County, Hainan Province

#### **ASEAN Production Base:**

Negeri Sembilan, Malaysia

# **Singapore Production Base:**


West Region, Singapore

#### Saudi Arabia Production Base:

Riyadh, Saudi Arabia

Sales Hotline: 0086-760-88589004 E-mail: geto\_market@geto.com.cn





# **Company Profile**

GETO is mainly engaged in green construction and new energy.


Green prefabricated building products include aluminium formwork, steel formwork, steel-framed timber formwork, climbing systems, fair-faced concrete formwork, infrastructure formwork and scaffolding products; prefabricated steel structures, assembly precast concrete components, and modular building (including PC and steel structures).

The main focus of new energy is investment, construction, and operation of "Photovoltaics, Storage, and Charging" projects, while providing the "Green Energy Future Living" one-stop residential energy solution.

In 2021, GETO was listed on the ChiNext board of the Shenzhen Stock Exchange in China. We have established 12 production bases around the world and registered 32 international trademarks in different countries and regions.








|       |   |      |          |   | PAGE |
|-------|---|------|----------|---|------|
| Table |   |      | 4        | Illustration Of Frame<br>System                         | 14   |
| CO    | ntent   | PAGE |          | 4.1 Setting installa - tion platform                    | 15   |
|       | Enterprise Size                                   | 03   |          | 4.2 Install First Walkway<br>Plate                      | 15   |
| T     | -   |      |          | 4.3 Installation of Poling                              | 17   |
|       | 0.1 GETO Production<br>Bases                      | 03   |          | 4.4 Installation of Second                              | 18   |
|       | 0.2 Cooperation Area                              | 03   |          | Walkway Plate  4.5 Installation of Protective           | 10   |
|       | 0.3 Overseas Markets                              | 04   |          | Net   | 19   |
|       |   |      |          | 4.6 Set up Inside Closed<br>Turning Plate               | 20   |
| 1     | Summary For GT-18 Self Climbing Platform          | 06   |          | 4.7 The end of the Frame Fragment Protection            | 21   |
|       | 1.1 Lifting System                                | 07   |          | 4.8 Installation of Skirt - ing Board                   | 21   |
|       | 1.2 Frame System                                  | 09   |          |   |      |
|       | 1.3 Lightning Protection System                   | 09   | <b>5</b> | Installation of Attached Support                        | 22   |
|       | 1.4 Attached support<br>System                    | 10   |          | System  |      |
|       | 1.5 Control System                                | 11   |          | 5.1 Installation of Attached<br>Support                 | 23   |
| 2     | Application Scope and Condition                   | 11   | 6        | Installation of Lifting<br>System                       | 25   |
|       | 2.1 Application Scope                             | 11   |          |   |      |
|       | 2.2 Application Condition                         | 11   |          | 6.1 Installation of Slide-Way                           | 25   |
|       |   |      |          | 6.2 Installation of Upper and Lower Hanger Frame        | 26   |
| 3     | Installation Process                              | 12   |          | 6.3 Installation of Lifting<br>Hanging Bracket          | 27   |
|       | Site Installation Process of Climbing Scaffolding | 13   |          | 6.4 LoadSensorand Electric<br>Chain Hoist Installa tion | 28   |



|   |   | PAGE |           | P.A  | \GE |
|---|---|------|-----------|--|-----|
| _ | Installation and Use of Control System  | 29   |           | Precautions for Use  | 44  |
| 7 | 7.1 Installation of Electrical Control System   | 30   | 10        | 10.2/A.1.4 GT-18 Self<br>Climbing Platform Lifting<br>Checklist  | 46  |
|   | 7.2 Control Operation of Electrical System  | 30   |           | 10.2/A.1.5 Self-checking<br>list for GT-18 Self Climbing<br>Platform adhesive lifting<br>scaffolding after the falling | 48  |
| 8 | Lightning Protection<br>System Installation   | 32   |           | 10.9/GT-18 Self Climbing<br>Platform month checklist   | 50  |
|   | 8.1 The lightning protection system consists of a lightning receptor, lightning protection net and grounding wire | 33   |           | 10.9/Monthly mainte-<br>nance schedule   | 50  |
|   | 8.2 Attention when setting  | 33   |           | High Altitude Removal  | 51  |
|   | lightning protection devic-<br>es   |      | 11        | 11.1 Preparation before dismantling  | 52  |
| 9 | Correct Operation of the<br>GT-18 Self Climbing<br>Platform   |      |           | 11.2 Dismantling process   | 52  |
|   | racionii  | 34   |           | 11.3 Precautions   | 53  |
|   | 9.1 GT-18 Self Climbing<br>Platform lifting process   | 35   | 12        | GT-18 Self Climbing<br>Platform Installation and<br>Common Use Tools   | 54  |
|   | 9.2 After the installation of the frame is completed, notify Party A to check and accept                          | 36   |           | List of Tools for Installa-<br>tion of GT-18 scaffolding   | 55  |
|   | 9.3 scaffolding lifting (or   |      | 10        | Advantages   | 58  |
|   | lowering) must be approved by Party A   | 39   | <b>13</b> | 13.1 Advantages  | 59  |
|   |   |      |           | 13.2 Production Comparison   | 59  |
|   | 9.4 Pre-tightening elec-<br>tric chain hoist steps<br>and methods   | 43   |           | 13.3 Personal Protective<br>Equipment  | 61  |
|   | 9.5 GT-18 Self Climbing<br>Platform requirements for use  | 43   | 14        | Project References   | 62  |



#### GETO Production Base:

# **South China Production Base:**

Jiangmen, Guangdong, China

# **East China Production Base 1#:** Guangchang, Jiangxi, China

**East China Production Base 2#:** Guangchang, Jiangxi, China

# **Central China Production Base:**

Xianning, Hubei, China

#### **North China Production Base:**

China aluminium formwork industrial park, Weifang, Shandong, China

#### **Hainan Free Trade Port Prefabricated Construction Base:**

Lingao, Hainan, China

# **Malaysia Production Base:**

Lot 143, 145, Jalan Permata 1/5, Arab Malaysian Industrial Park, 71800 Nilai, Negeri Sembilan

# Cooperation Area

With a spirit of craftsmanship and perfection, under the call of national "Belt and Road", and adhering to the service tenet of "creating value for customers", we have established long-term partnership with China Top 10 construction companies, such as CSCEC, CREC, MCC, ZHONGTIAN Group, and Country Garden, Vanke, Greenland, Poly, Evergrande Group, etc



# **Overseas Markets**



# Headquarter

Greater Bay Area—No. 13 Heqing Road, Tsuihang New District, Zhongshan City, Guangdong Province

# Singapore GE10

Blk 808 French Road #05-157 Kitchener Complex, Singapore

# **Malaysia GETO**

No 1-2 (Second Floor), Jalan Anggerik Vanilla BF 31/BF, Kota Kemuning, 40460 Shah Alam, Selangor Darul Ehsan, Malaysia

GT18 Self Climbing Platform





# **Summary For GT-18 Self Climbing Platform**

GT-18 Self Climbing Platform is a new scaffolding system developed in recent years, which is predominantly suitable for high-rise buildings and super high-rise buildings. It can rise along with buildings. This system is a technological innovation in the field of scaffolding. For instance, it is not necessary to overhang i-steel for numerous times. Next, it exempts the disassembly and assembly process of the scaffolding.

(After one round of assembly, it can be used until the construction ended). Likewise, it is not limited by the height of the building. Hence, this greatly saved the usage of human resources and materials. GT-18 has more safeguards and plays a greater advantage in high-rise buildings by comparing it with the traditional method of scaffolding.



# **Components of Self Climbing Platform**











**Lifting System** 

**Frame System** 

**Lightning Protection System** 

Attached Support System

**Control System** 




# 1.1 Lifting System

Self Climbing Platform

(commonly known as: climbing frame) is the extension and development of the external scaffolding. It is a complete set of construction equipment developed from the traditional concept of building turnover materials. It possesses all the functions of traditional scaffolding, specifically suitable for high-rise buildings and super high-rise buildings. The lifting system consists of slideway, lifting hanging bracket, lower hanger frame, electric


chain hoist, and over hanger frame.

GT-18 Self Climbing Platform is one unique kind of scaffolding. It consists of frame system, attached support system, lifting system, control system and lightning protection system. GT-18 Self Climbing Platform is suitable for high-rise and super-high-rise buildings with frame or shear wall structures. Through the application in different sites, it has been proved that its performance is excellent, safe, reliable, stable operation, economic and practical, which brings great convenience to the construction and production formost users.






The lifting system consists of slideway, lifting hanging bracket, lower hanger frame, electric chain hoist, and over hanger frame.



# 1.2 Frame System

Frame system is the main component of attaching lifting scaffolding, and also the safe operation platform for constructors. The frame structure is mainly composed of walkway plate, poling, protective net, truss, turning plate etc.



# 1.3 Lightning Protection System

The system consists of air termination, grounding grid and grounding wire.


Note: The high-rise construction lifting platform type high-rise metal frame, which is close to the reinforced concrete structure, is extremely vulnerable to lightning strikes, so lightning protection measures are very important. Every time the frame body is lifted, the grounding cable connecting the frame of the high-rise construction lifting platform and the main body of the building must be removed, and then lifted. After the lifting is completed, connect the frame and the building with a grounding cable of not less than  $\phi 16 \text{mm}^2$ .






# 1.4 Attached Support System

The attached support system is a supporting structure that is directly attached to the building structure and connected to the vertical main frame to withstand and transmit loads. With support, anti - fall, anti - capsize function.



# 1.5 Control System

To form the control system, some essential components are computer, mobile phone, tablet PC, remote controller, sensor main control box, sub-control box, cable line and loading sensor.



# **Application Scope and Condition**

# 2.1 Application Scope

Suitable for industrial and civil (frame, shear wall structure) high-rise buildings


Application Scope and Condition

# 2.2 Application Condition

Each project is necessary to design the subject construction method statement.


Each project must meet the requirements of "Technical Standard for Safety of Construction Tool Scaffolding".

GT-18 Self Climbing Platform is prohibited from lifting operations in gale above grade 5 (including grade 5), heavy rain, heavy snow, foggy days and nights.



# **Installation Process**

# **Site Installation Process Of Climbing Scaffolding**





# **Setting Installation Platform**

# 4.1 Setting Installation Platform

Party A assemble a platform by steel pipe and clamp on the installed flat( Party A assembled according to our requirements and need to pass our acceptance).

Assemble standard:(1) installation platform shall start form the typical floor,platform width need to be control within 1.2M-1.5M.

The distance between the installation platform and the pole is not more than 1.5m, the step of the large crossbar is not more than 1.4m, and the inner row is 0.2m to 0.3m from the outer edge of the building structure.


Reinforcement measures shall be taken when the platform is set up. A set of horizontal tie rods every three meters shall be set at the top of the platform or the position of the lower step frame to unload and reinforced. (Fig.4.1.1)



4.2.1 Assemble on the ground leveling site or erect directly on the platform. Place the bottom walkway board on the bottom of the platform and bolt it together as shown in the figure (Fig. 4.2.1).



(Fig. 4.1.1)




(Fig. 4.2.1)



# 4.2.2 Set up bottom joint of frame:

Installation standard: wearing safe belt. The connected walkway board is placed in parallel with the structure, the distance between the edge of the walkway board and the wall is installed according to the distance requirement of the shop drawing, and the walkway board is fixed on the installation platform by clamp and cross bars. After installing the pole, no less than 2 wall-attaching joint per 20m.(Fig. 4.2.2)



| S/N | Description               | Model No.              | Qty                  | Remark  |
|-----|---------------------------|------------------------|----------------------|---|
| 1   | Walkway plate             | Standard specification | Configure as request |   |
| 2   | Connecting plate          | Standard specification | Configure as request |   |
| 3   | Electric wrench           | XL-80032               | 1                    | One person standard   |
| 4   | Sleeve                    | 22mm、24mm              | Each 1               | Use with electric wrench  |
| 5   | Manual wrench             | 24mm                   | 1                    | One open-ended and plum<br>combined wrench<br>(one person standard) |
| 6   | Matching hexago-nal bolts | M16×50                 | Configure as request | 1 bolt +1 nut+1 spring<br>washer+2 flat washer=1 set                |

# 4.3 Installation of Poling

# 4.3.1 Installation of interior poling

According to the shop drawing marked size install the poling fixing on the walkway plate (Fig.4.3.1), using M16 x 100 hex bolt with flat washer, spring washer, nut connecting the poling fixing part on the first and second hole of poling bottom.

#### **Bolt installation standard:**


wearing safe belt. 1 spring washer, 2 flat washer, 1 M16 x 100 bolt and 1 nut consist 1 set. Ensure that at least 3 teeth are exposed during installation.



(Fig. 4.3.1)

# 4.3.2 Installation of exterior poling

According to the construction drawing marked size install the exterior poling, The first hole of the poling bottom use M16 X 70 bolt with flat washer and nut connecting with walkway plate, interior and exterior poling connecting by angle truss, it is for temporary reinforcement, In this step, the internal and external bolts of the truss are not tightened, and maintained a little force. After the installation of the second floor walkway plate, the truss is removed and the triangle truss is re-installed according to the construction shop drawings.



(Fig. 4.3.2)

#### Installation standard:

wearing safe belt. 1 spring washer, 2 flat washer, 1 M16 x 70 bolt and 1 nut consist 1 set. Ensure that at least 3 teeth are exposed during installation. Without the first attachment support, at least one fixed connecting rod should be reserved in four positions during erection to maintain the stability of the frame.



(Fig. 4.3.3)





# **Materials and Tools**

| S/N | Description          | Model    | Qty                  | Remark   |
|-----|----------------------|----------|----------------------|--|
| 1   | Poling               | 3m/4.5m  | Configure as request |  |
| 2   | Electric wrench      | XL-80032 | 1                    | One person standard  |
| 3   | Sleeve               | 24mm     | 1                    | Use with electric<br>wrench                                  |
| 4   | Manual Wrench        | 24mm     | 1                    | One open-ended and plum combined wrench(one person standard) |
| 5   | Matching Hex bolt    | M16×80   | Configure as request | 1 bolt +1 nut+1 spring washer<br>+2 flat washer=1 set        |
| 6   | Fixed connecting rod | Ф48      | Configure as request |  |

# 4.4 Installation of Second Walkway Plate

Installation of interior poling

According to the shop drawing marked size install the poling fixing on the walkway board (Fig.4.3.1), using M16 x 100 hex bolt with flat washer, spring washer, nut connecting the poling fixing part on the first and second hole of poling bottom.

Installation standard: Wearing safe belt, M16 \*100 bolts are used for the erection of the poling fixed and the poling. M16 \*40 bolts are used for the connection between the walkway board and the poling fixed. M16 \*70 bolts are used for the connection between the walkway board and the external poling. M16 \*40 bolts are used for the connection between the walkway board and the walkway board. Walkway boards are installed on both sides of the connecting plate, and M16 \*40 bolts are used for the connection between the walkway board and the connecting plate. 1 spring washer, 2 flat washer, 1 M16 bolt and 1 nut consist 1 set. Ensure that at least 3 teeth are exposed during installation. (Fig.4.4.1)




(Fig. 4.4.1)

# 4.5 Installation of Protective Net

According to the construction shop drawing, use the M16 $\times$ 70 bolt to reinforce the frame connection bracket on the corresponding position on the pole. Do not lock it first, then fix the protection net on the frame connection bracket through the 7-shaped bolt, and then lock it.

# Installation standard:

Wearing safe belt,1 spring washer, 2 flat washer, 1 M16 bolt and 1 nut consist 1 set. Ensure that at least 3 teeth are exposed during installation. The frame connector is straight and the 7-shaped bolt is spread out on both sides. (Fig.4.5.1)



| S/N | Description              | Model                  | Qty | Remark   |
|-----|--------------------------|------------------------|-----|--|
| 1   | Electric wrench          | XL-80032               | 1   | One person standard  |
| 2   | Sleeve                   | 24mm                   | 1   | Use with electric wrench                                     |
| 3   | Manual Wrench            | 24mm                   | 1   | One open-ended and plum combined wrench(one person standard) |
| 4   | Matching Bolt            | M16×80                 | 1   | 1 bolt +1 nut+1 spring washer<br>+2 flat washer=1 set        |
| 5   | Protection Net           | Standard specification | 1   | QTY for single protection net                                |
| 6   | Frame connection bracket | Standard specification | 4   | QTY for single frame connection bracket                      |
| 7   | 7-shaped Bolt            | Ф10×120                | 4   | QTY for single frame connection bracket                      |



# 4.6 Set up Inside Closed Turning Plate

In the bottom of GT-18 Self Climbing Platform and the third floor of the uniform structure (also according to the requirements of the scheme), a turning plate and an extension plate are installed between the inside of the walkway plate and wall. The extension plate and the walkway board are connected by M16 \*40 bolts, and the turning plate is connected by standard parts and plate hinge.(Figure 4.6.1) Installation standard:

- 1. Wearing safe belt.
- 2. When installing the inner extension plate and turning plate, it can be cut on the site according to the actual situation when necessary.
- 3. The extension plate and turning plate should be set continuously along the external structural plane of the building.
- 4. Ensure that the frame and the structure close sealing after the installation of the extension plate and the turning plate is completed, and prevent accidents such as falling persons and objects.
- 5. The extension plate is fixed on the walkway board with M16 \*40 bolt in the field. The turning plate is installed within 10 mm from the outer edge of the extension plate. Hexagonal flange self-tapping nail (ST4.8 x 19) is used to fix the hinge on the extension plate.



(Fig. 4.6.1)

| S/N | Description                           | Model       | Qty                  | Remark   |
|-----|---------------------------------------|-------------|----------------------|--|
| 1   | Extension plate                       |             | Configure as request |  |
| 2   | Turning plate                         | 1.5M        | Configure as request |  |
| 3   | Hexagonal flange<br>self-tapping nail | ST5.5×25    | Configure as request |  |
| 4   | Matching bolt                         | M16×50      | Configure as request | 1 bolt +1 nut+1 spring washer<br>+2 flat washer=1 set        |
| 5   | Electric Wrench                       | XL-80032    | 1                    | One person standard  |
| 6   | Sleeve                                | 24mm、8mm    | Each 1               | Use with electric wrench                                     |
| 7   | Manual Wrench                         | 24mm        | 1                    | One open-ended and plum combined wrench(one person standard) |
| 8   | Angle grinder                         | S1M-HS1-100 | 1                    | Equipped one box of cutting slices                           |

# 4.7 The end of the Frame Fragment Protection

The fragment are protected by shaped protective net, and the protection net at the corridor entrance without permission after installation. (Fig. 4.7.1) Installation standard:

Wear safe belts for installation. For convenience, it is preferable to install the 7-shaped bolt on the outer side of the rack, and then install the 7-shaped bolt on the inner side of the rack.



(Fig. 4.7.1)

# **Materials and Tools**

| S/N | Description        | Model    | Qty                  | Remark |
|-----|--------------------|----------|----------------------|--------|
| 1   | End protection net | 700×1500 | Configure as request |        |
| 2   | 7-shaped bolt      | Ф10×120  | Configure as request |        |

# 4.8 Installation of Skirting Board

To installed skirting board between the walkway plate and protection net when set turning plate in the frame.

Installation Standard:

Wear seat belts for installation. The installation of the skirting board should be tight, and the outer side should be close to the protective net, and the gap no more than 10 mm. When encountering interference with the pole, the opening can be avoided according to the situation to ensure the outer side is tightly closed. Under the skirting board, fix it on the outside of the skirting board with ST4.8 19 self-tapping nails. Skirting board shall be installed in a smooth way without warping and deformation (as shown in Fig. 4.8.1).



(Fig. 4.8.1)


| S/N | Description                        | Model       | QТY                  | Remark                             |
|-----|------------------------------------|-------------|----------------------|------------------------------------|
| 1   | Skirting board                     | 1.41M       | Configure as request |                                    |
| 2   | Electric Wrench                    | XL-80032    | 1                    | One person standard                |
| 3   | Sleeve                             | 8mm         | 1                    | Use with electric wrench           |
| 4   | Hexagonal flange self-tapping nail | ST5.5×25    |                      |                                    |
| 5   | Angle grinder                      | S1M-HS1-100 | 1                    | Equipped one box of cutting slices |



# **Installation of Attached Support System**

# 5.1 Installation of Attached Support

Before erecting section 2 slide-way, attaching support base jack shall be installed on the frame. Firstly, inspect the pre-embedded holes are on the right position, and then the attachment support is installed in the pre-embedded holes of the structure with M30 high strength screw. Each end of the screw is equipped with one 100 x 100 x 10 Square backing plate and 2 nuts. The splints on both sides are clamped into the slide-way, and the splints are installed on the upper and lower splints of the attaching support base jack through the pin shaft of  $\phi$ 16×55 (Fig. 5.1.1). The top support and double torsion spring are installed on the surface of the attaching support base jack to make the top support stick to the slide-way. Adjust the adjusting screw of the top support to make the top support pressed on the selector.



(Fig. 5.1.1)

# **Installation Standard:**

Wear seat belts for installation. Attachment support is installed on the outer side of the wall. The center line of the embedded hole is aligned with the center line of the slide-way, and the horizontal deviation is less than 10 mm. The movable attachment support adjusts the relative position of the attachment support and the slide-way. The tie rod nut through the wall can be tightened only after the support and cushion plate are attaching to the wall. The tie rod is forbidden to be unloaded or falsely loaded. After the backing plate is filled with the structure, the nut must be tightened to prevent loosening. The double toe rod fixed on each attachment support, and the square backing plate must be positioned horizontally. Double nuts on both sides of the tie rod, expose 3 buckle teeth or no less than 10mm. After installation, butter lubrication is applied on the contact surface between the splint and the slide-way. 3 attaching support base jack should be installed in the vertical direction of each slide-way in operation mode, and no less than 2 in lifting or descending operation mode.




(Fig. 5.1.2)



| S/N | Description                 | Model                                   | Qty | Remark                                     |
|-----|-----------------------------|---|-----|--|
| 1   | Matching manual wrench      | One open-ended and plum combined wrench | 1   | 2 persons standard                         |
| 2   | Attaching support base jack | Configure as request                    | 3   |  |
| 3   | Top support                 | Configure as request                    | 3   |  |
| 4   | High Strength tie rod       | M30XL                                   | 6   | 1 tie rod+ 2 backing plate+4<br>nuts=1 set |
| 5   | Guide wheel frame           | Configure as request                    | 6   |  |
| 6   | Pin shaft                   | Ф16×55                                  | 12  |  |






# 6.1 Installation of slide-way

According to the Framing Module layout requirements, the first hole at the lower end of the slide-way is connected with the position hole of the slide-way of the walkway plate by M16 \*40 hexagonal bolt. When the two slide-way are connected, the connecting plate is needed to reinforce them.



# **Installation of Lifting System**



(Fig. 6.1.1)

Installation Standard: Wear seat belts for installation. M16 \*40 bolts are used to connect the walkway plate with the slide-way; M16 \*70 high strength bolts are used to connect the slide-way with the slide-way, and double nuts are used; M16\*40 bolts are used to connect the slide-way with the connecting plate. Due to the excessive weight of the slide-way itself, pay attention to safety during installation. 1 spring washer, 2 flat washer, 1 nut(use double nut in connect place of 2 slide-way) and 1 M16 bolt consist of 1 set, Make sure that at least 3 buckle teeth are exposed during installation. After installation, butter is applied on the contact surface between slide-way and splint. (Fig. 6.1.1)


| S/N | Description        | Model    | Qty                  | Remark   |
|-----|--------------------|----------|----------------------|--|
| 1   | Slide-way          | 4.5m/6m  | Configure as request |  |
| 2   | Electric wrench    | XL-80032 | 1                    | One person Standard  |
| 3   | Sleeve             | 24mm     | 1                    | Use with electric wrench                                     |
| 4   | Manual wrench      | 24mm     | 1                    | One open-ended and plum combined wrench(one person standard) |
| 5   | Matching hex bolt  | M16×50   | Configure as request | 1 bolt +1 nut+1 spring washer<br>+2 flat washer=1 set        |
| 6   | High strength bolt | M16×70   | Configure as request | 1 bolt +2 nut+1 spring washer<br>+2 flat washer=1 set        |



# 6.2 Installation of Upper and Lower Hanger Frame (Fig6.2.1)

Installation of Lower Hanger Frame: According to the drawing design, the hanger fixing piece and the lower hanger are reinforced together by M16 bolts and filled with bolts (as shown in Figure 6.2.2).

Installation of Upper Hanger Frame: According to the drawing design, the hanger fixing piece and the upper hanger are reinforced together by M16 bolts and filled with bolts (as shown in Figure 6.2.3).




| S/N | Description       | Model                | Qty                  | Remark   |
|-----|-------------------|----------------------|----------------------|--|
| 1   | Electric wrench   | XL-80032             | 1                    | One person Standard  |
| 2   | Sleeve            | 24mm                 | 1                    | Use with electric wrench                                     |
| 3   | Manual wrench     | 24mm                 | 1                    | One open-ended and plum combined wrench(one person standard) |
| 4   | Matching hex bolt | M16×50               | Configure as request | 1 bolt +1 nut+1 spring washer<br>+2 flat washer=1 set        |
| 5   | Lower hanger      | Configure as request | 1                    | QTY for single framing module                                |

# 6.3 Installation of Lifting Hang ing Bracket

Fix the lifting hanging bracket on the building structure with 2 high-strength screw, tighten the nut internally after adjusting the position, and tighten the external nut. The two ends of the screw leak out of the double nut at least 3 buckle teeth(no less than 10mm) (Fig. 6.3.1).

Installation Standard: Wear safty belts for installation. Installation to ensure that the lifting hanging bracket is vertical, both inside and outside are equipped with  $100 \times 100 \times 10$  backing plate, screw inside and outside must have 2 nuts.



(Fig. 6.3.1)

| S/N | Description                | Model                                   | Qty | Remark                                   |
|-----|----------------------------|---|-----|--|
| 1   | Matching manual wrench     | One open-ended and plum combined wrench | 2   | 2 persons standard                       |
| 2   | High strength screw        | M30XL                                   | 2   | 1 bolt+ 2 backing plate + 4<br>nut=1 set |
| 3   | Lifting hanging<br>bracket | Standard specification                  | 1   |  |
| 4   | Loading pin shaft          | 24mm                                    | 1   | attaching split pin                      |




# 6.4 Load Sensor and Electric Chain Hoist Installation

Load sensor is installed at the hanging point of the lower hanger frame, which is tightened and strengthened with M30 \*120 high strength standard bolts, nuts, spring washer and flat washer. (Figure 6.4.1)

The electric chain hoist hook is hung in the hanging hole above the sensor, and the upside chain unit of the electric chain hoist is installed on the upper hanger. (Figure 6.4.2)

#### Installation Standard:


Wear seat belts for installation. When the electric chain hoist is suspended, the wire that binds the chain is not allowed to be dismantled. After the complete installation, the chain should be dismantled. The chain should be straightened out. There should be no phenomenon of chain flipping, twisting, knotting and crossing rings that affect the operation. After the installation, butter should be applied to the chains, springs, screw and other positions.





(Fig. 6.4.2)

| S/N | Description            | Model     | Qty | Remark   |
|-----|------------------------|-----------|-----|--|
| 1   | Matching Manual wrench | 46mm/41mm | 2   | One end 46mm and another end 41mm (2 persons standard) |
| 2   | Load sensor            | 10T       | 1   |  |
| 3   | Electric chain hoist   | 7.5T      | 1   |  |
| 4   | High strength screw    | M30×120   | 1   | 1 bolt+ 2 backing plate + 4<br>nut=1 set               |





# **Installation and Use of Control System**

# Installation of Electrical Control System

The electrical installation of GT-18 Self Climbing Platform should strictly comply with the provisions of "Code for Safety of Power Supply in Construction Site" GB50194 and "Technical Code for Safety of Temporary Electricity Use in Construction Site" JGJ46.

- 7.1 The cable is protected by special PVC groove, fixed on the protective network of the lower side of the second walkway board, and the main cable is distributed within the same height. The reserved length of the cable should meet the requirement of raising the height of one layer. The cable joint must be securely tied by insulating waterproof tape, and the connection should be firm and reliable, so as to avoid false connection and leakage connection.
- 7.2 Main Control Box and Sub-control Box should be waterproof. The main control box and sub-control box shall meet the safety requirements of grounding and leakage protection, and the main control box and sub-control box shall be installed in the first step of the frame.
- 7.3 The control mode of electrical system is divided into automatic control (remote control) and manual control.

Automatic control refers to the use of remote to control the main control box, so as to achieve the controlling the rotation of each electric chain hoist. Manual control refers to the failure of some positions, which affects the overall lifting of the whole rack. At this case, it is necessary to control the operation of a certain position separately, eliminate the failure and ensure the overall lifting of the rack.

Connecting the wire-controlled air plug with the air socket of the control box, the remote controller can be used to control the forward, reverse and stop of the electric chain hoist.



| S/N | Description                                   | Model  | Qty                     | Remark                            |
|-----|---|--|-------------------------|-----------------------------------|
| 1   | Mai control box                               | Standard specification   | Configure<br>as request |                                   |
| 2   | Sub-control box                               | Standard specification   | 1                       | QTY for single framing module     |
| 3   | Cable   | Standard specification   | Configure as request    |                                   |
| 4   | PVC groove                                    | Standard specification   | Configure<br>as request |                                   |
| 5   | Cable ties                                    | 5X400  | Configure<br>as request |                                   |
| 6   | Controller                                    | Standard specification   | 1                       |                                   |
| 7   | Electrician knife                             | 10-225-23  | 1                       |                                   |
| 8   | Multimeter                                    | 3280-10F   | 1                       |                                   |
| 9   | Test pencil                                   | MNT -111302  | 1                       |                                   |
| 10  | Insulating<br>waterproof tape                 | 25x500mm   | 10                      | Insulation before waterproof tape |
| 11  | Electrical insulat-<br>ing tape               |  | 10                      |                                   |
| 12  | Vice  | FO-2603A   | 1                       |                                   |
| 13  | Wire stripper                                 | LA815138   | 1                       |                                   |
| 14  | Slot type screw-<br>driver                    | JX-0189  | 1                       |                                   |
| 15  | Phillips screw-<br>driver                     | JX-0189  | 1                       |                                   |
| 16  | Scissors                                      | 45-degree angle scissors<br>multifunctional electrical trough<br>scissors universal PVC scissors |                         |                                   |
| 17  | Electric Box Installa<br>tion Auxiliary Frame |  |                         |                                   |



Sughtning Protection System Installation

## **Lightning Protection System-In stallation**

### 8.1 The Lightning Protection System Consists of A Lightning Receptor, Lightning Protection Net and Grounding Wire.

8.1.1 Lighter (i.e. lightning rod) Made of  $\phi$ 12 × 1200 galvanized steel.

#### 8.1.2 Lightning protection net

All the lightning receptors on the uppermost layer are connected by  $40 \times 4$  galvanized flat iron to form a lightning protection net.

#### 8.1.3 Ground wire

Set a grounding wire within 50m of the continuous length of the climbing frame, and meet the requirements of the transition resistance of the climbing frame  $\leq 10\Omega$  and the grounding resistance  $\leq 20\Omega$  at the farthest point from the grounding wire. A grounding wire is arranged under the pole, and the grounding wire is connected to the lightning protection grounding point of the construction structure by a grounding cable with a diameter of not less than 16 mm2.






### 8.2 Attention When Setting Lightning Protection Devices


1. After the frame is installed, the lightning protection measures and lightning protection devices during the thunderstorm season should be done.

- 2. The grounding mode and position selection, lightning protection net and grounding wire arrangement, material selection, connection method, fabrication and installation shall be installed in accordance with the "Lightning Protection Design Code for Buildings" GB50057-94. After installation, the resistance meter shall be used for determination, see whether it meets the "Technical Specifications for Building Lightning Protection Devices".
- 3. The position of the grounding wire should be selected where people can't easily touch it to avoid and reduce the risk of stride voltage, prevent the grounding wire from being mechanically damaged, and keep the grounding wire at a safe distance of 3m or more from other metals or cables.
- 4. In case of thunderstorm during construction, the personnel on the frame should be evacuated immediately (to prevent personal injury caused by lightning strikes).



# Correct Operation of the GT-18 Self Climbing Platform

### 9.1 GT-18 Self Climbing Platform lifting process





## 9.2 After The Installation of the Frame Is Completed, Notify Party A To Check and Accept

For specific matters, check the "GT-18 Self Climbing Platform First Installation Inspection Acceptance Form"

| P                     | roject                               |  |                             | Construction area (m²) |                   |
|-----------------------|--------------------------------------|--|-----------------------------|------------------------|-------------------|
| Stru                  | ıcture                               | Structure floo   | or                          | Maximum<br>height (m²) |                   |
|                       | nber of<br>Chine                     | promotion<br>and demotio<br>grouping                                   | n                           | Usage                  |                   |
| Mai                   | n contractor                         |  |                             | Project manager        |                   |
| Clie                  | nt                                   |  |                             | Project manage         |                   |
| Spec<br>editi<br>tion | ial program<br>ng produc-<br>company |  |                             | Project manager        |                   |
|                       | allation<br>npany                    |  |                             | Project manage         |                   |
| S/N                   | Inspection items                     | Inspection   | n contents                  |                        | Inspection result |
| 1                     |                                      | Frame height≤5 times storey heigl                                      | nt, Frame width≤1.2m        |                        |                   |
| 2                     |                                      | Support span (straight type)≤7 m<br>Support span (the distance outside | the fold line or curved fra | me) ≤ 5.4m             |                   |
| 3                     | Scaf-                                | Full height of the frame $\times$ support                              | span ≤110 m2                |                        |                   |
| 4                     | folding<br>Size                      | Horizontal cantilever length ≤ 2m,                                     | and ≤ 1/2 adjacent suppo    | ort span               |                   |
| 5                     |                                      | The poling, the longitudinal horizo intersect with the major node.     | ntal bar and the transverse | e horizontal bar       |                   |
| 6                     |                                      | Poling spacing and cross bar spacing and current relevant standards.   | ng are in accordance with t | he specifications      |                   |
| 7                     |                                      | Component layout conforms to the                                       | instructions                |                        |                   |
| 8                     | Vertical                             | The specifications and dimensions instructions for use.                |                             |                        |                   |
| 9                     | main<br>frame                        | Each joint is welded or bolted.  |                             |                        |                   |
| 10                    |                                      | The vertical deviation ≤5‰, and ≤                                      |                             |                        |                   |
| 11                    |                                      | The height difference of adjacent v                                    | ertical main frames≤20mr    | m                      |                   |

| S/N | Inspection items     | Inspection contents  | Inspection result |
|-----|----------------------|--|-------------------|
| 12  |                      | Component layout and specification conforms to the instructions  |                   |
| 13  | Horizontal support   | Each joint is welded or bolted.  |                   |
| 14  |                      | Poling spacing is in accordance with the specifications and current relevant standards   |                   |
| 15  |                      | Component layout and specification conforms to the instructions and current relevant standards   |                   |
| 16  | Frame<br>structure   | No missing parts of the frame and reliable connection  |                   |
| 17  |                      | The poling, the longitudinal horizontal bar and the transverse horizontal bar intersect with the major node.   |                   |
| 18  |                      | Connecting nodes conform to specifications and current relevant standards  |                   |
| 19  | Scaffold-            | Bearing capacity and deformation of scaffoldings conform to special safety construction scheme   |                   |
| 20  | ing                  | The bottom is laid tightly, and there is no gap with the building.   |                   |
| 21  |                      | The operation layer is covered and laid firmly, the diameter of the tangential circle in the hole <25mm, and the length of the scaffolding probe ≤150mm.   |                   |
| 22  |                      | Attachment support shall be provided for each floor covered by the vertical main frame.  |                   |
| 23  |                      | Attachment support shall be connected with building structure by no less than two bolts, and the bolt diameter meets the design requirements.  |                   |
| 24  |                      | attaching support base jack and building structure are tightly combined and fastened   |                   |
| 25  | Attaching            | The age compressive strength of concrete at the joints meets the design requirements and $\geqslant\!15\text{MPa}$   |                   |
| 26  | support<br>base jack | Distance from center of bolt hole to bottom of beam (>150 mm)  |                   |
| 27  |                      | The exposed length of the bolt is more than 3 times the pitch and more than 10 mm. Size of backing plate (> $100 \times 100 \times 100$ mm)  |                   |
| 28  |                      | It has anti-tilt and guiding functions.  |                   |
| 29  |                      | Using operation mode, the frame body is fixed on the attachment support  |                   |
| 30  |                      | Facade full of bridging  |                   |
| 31  | Bridging             | The horizontal angle of the scissors is $45^{\circ} {\sim} 60^{\circ};$ it is reliably connected with the frame rod  |                   |
| 32  |                      | When the steel mesh frame is used to replace the bridging in the diagonal bar, the rigidity and strength of the diagonal bar are not lower than the rigidity and strength of the bridging, and the connection with the frame body should be ensured. |                   |



| S/N                   | Inspection items  |  | Inspection contents                                       |   |                     | Inspection<br>result |  |
|-----------------------|---|--|---|---|---------------------|----------------------|--|
| 33                    |   | Anti-overturning rails are reliably connected to the vertical major frame                                |   |   |                     |                      |  |
| 34                    | Anti-over-<br>turning<br>equip-   | For lifting conditions, the minimum guides is ≥ 2.8m, or ≥ 1/4 height; uppermost and lowermost anti-tilt | the working condition, the spaci                          | ng between the  |                     |                      |  |
| 35                    | ment  | The gap between the guid   | e and the guide rail is ≤                                 | 5mm   |                     |                      |  |
| 36                    |   | Each machine position is rused in both use and lifting   |   | i-drop devices, and can b                               | e                   |                      |  |
| 37                    | Anti-drop<br>devices  | anti-drop devices has dust<br>sensitive and reliable   | proof and anti-pollutior                                  | n measures, and is                                      |                     |                      |  |
| 38                    |   | When only one anti-drop of device should be connected  | levice is provided for one<br>ed to the different wall so | e position, the anti-drop<br>upport with the lifting de | vice.               |                      |  |
| 39                    |   | The steel boom of the boo<br>tion and diameter is ≥ 25 r   |   | es is determined by calcu                               | la -                |                      |  |
| 40                    | Synchro-  | Tooled scaffolding with re   | stricted load control syst                                | tem   |                     |                      |  |
| 41                    | nizer   | It has the functions of con-<br>overload and load loss, rea  | trolling lifting and lower<br>al-time display and stora   | ing, automatic alarm and<br>age of load, and self-fault | d stop of<br>alarm. |                      |  |
| 42                    |   | The dense mesh safety ner<br>plate vertical mesh apertu  |   | <sup>2</sup> , and ≥3.5kg/sheet;Met                     | al                  |                      |  |
| 43                    |   | The facade is protected tig  | thtly and without gaps.                                   |   |                     |                      |  |
| 44                    | Protective  | When the dense mesh is used as th foot-board. When the framed meta with the frame and can withstand I    | I mesh is used as the safety net,                         | the metal frame should be reliab                        |                     |                      |  |
| 45                    | equipment   | When the working floor is high protective railing is in  | more than 2.0 meters av<br>stalled inside the frame.      | vay from the floor, a 1.2 r                             | n                   |                      |  |
| 46                    |   | The frame is broken or has vertical net  | a protective barrier at t                                 | he opening or closed wit                                | :h a                |                      |  |
| 47                    |   | The diameter of the inscribed circle should be less than 25mm; the scal body should be completely closed | folding board at the bottom of t                          |   |                     |                      |  |
|                       |   |  | Acceptance  |   |                     |                      |  |
| Inspection conclusion |   |  |   |   |                     |                      |  |
| Inspe                 | spector's signature Main contractor Client editing production Construct company |  |   |   |                     | uction company       |  |
|                       | Date:   |  |   |   |                     |                      |  |

### 9.3 Scaffolding Lifting (Or Lowering) Must Be Approved By Party A

Details refer to GT-18 Self Climbing Platform Pre-Lift inspection and acceptance form

| Pi                    | roject   |   | Operational type  | hoist             |  |  |  |
|-----------------------|--|---|---|-------------------|--|--|--|
| Work                  | king layer   | hoist height (m)  |   |                   |  |  |  |
| Main                  | contractor   |   | Project manager   |                   |  |  |  |
| (                     | Client   |   | Project manager   |                   |  |  |  |
| Spec<br>editi<br>tion | ial program<br>ng produc-<br>company                       |   | Project manager   |                   |  |  |  |
| Cons                  | truction<br>pany   |   | Project manager   |                   |  |  |  |
| S/N                   | Inspection<br>Item   | Inspection content  |   | Inspection result |  |  |  |
| 1                     | Concrete strength<br>at the attaching<br>support base jack | Reach the calculated value of the safety sp   | pecial construction plan, and ≥15MPa                                |                   |  |  |  |
| 2                     |  | Frame height≤5 times storey height, Fran  | ne width≤1.2m   |                   |  |  |  |
| 3                     |  | The frame has no structural changes, miss   | ing components, and damage.   |                   |  |  |  |
| 4                     | Scaffolding condition                                      | The components of the frame are connect connection is reliable.                       | ed without missing and the  |                   |  |  |  |
| 5                     |  | The unloading device at the vertical major can not use fastener or wire rope shall be | r frame shall not be less than 2, and used as the unloading device. |                   |  |  |  |
| 6                     |  | The safety protection facilities are not dar  | naged.  |                   |  |  |  |
| 7                     |  | attaching support base jack for each exist the vertical major frame                   | ing floor covered by  |                   |  |  |  |
| 8                     | Attaching<br>support<br>base jack                          | The anti-drop, anti-roll and guide devices support base jack are intact.              | on the attaching  |                   |  |  |  |
| 9                     | base jack  | attaching support base jack adapt double  | nut to reinforced.  |                   |  |  |  |
| 10                    |  | The lifting device is set up at the vertical n  | najor frame   |                   |  |  |  |
| 11                    | Lifting  | Lifting support adapt double nut to reinfo  |   |                   |  |  |  |
| 12                    | equip-<br>ment   | The connection of the lifting system components is not cracked, damaged,              |   |                   |  |  |  |
| 13                    |  | The lifting system is cleaned, maintained   | and runs smoothly   |                   |  |  |  |



| S/N                   | Inspection items                       |  | Inspection contents   |  |                                  | Inspection result     |
|-----------------------|--|--|---|--|----------------------------------|-----------------------|
| 14                    | Lifting                                | The power equipment corelevant standards, and the startup is sensitive, a    | the suspension is correc  | t. the connection is relia   | rent<br>ble,                     |                       |
| 15                    | equip-<br>ment                         | The control cabinet and functional.  | control equipment are v   | vorking properly and full  | ly                               |                       |
| 16                    |  | Each machine position is equipment, and it can fu                            | s not less than one set of<br>inction in both use and l                         | f anti-overturning ifting conditions.                                      |                                  |                       |
| 17                    | Anti-over-<br>turning                  | Anti-overturning equipm  | nent completed, Working   | g condition is normal  |                                  |                       |
| 18                    | equipment                              | After cleaning, inspectio sensitive and reliable.                            | n and maintenance, it is  | easy to operate,   |                                  |                       |
| 19                    |  | The installation position  | is correct and the stop i   | s effective.   |                                  |                       |
| 20                    | Anti-drop                              | For lifting conditions, the most guides is ≥ 2.8m, c distance between the up | e minimum distance bet<br>or ≥ 1/4 height; in the w<br>opermost and lowermost   | ween the uppermost and orking condition, the mile t guides is ≥ 5.6m, Or ≥ | d lower-<br>nimum<br>1/2 height. |                       |
| 21                    | device                                 | The cantilever height of   | the frame is ≤ 2/5, and   | ≤ 6m   |                                  |                       |
| 22                    | Obstacle                               | Obstacles and restraints   | of unobstructed scaffold  | ding are lifted  |                                  |                       |
| 23                    | Constraint removal                     | All the wall bars on the f   | rame are removed  |  |                                  |                       |
| 24                    | Operators                              | Hold a certificate and ha  | ive a Safety and Technol  | ogy Training record  |                                  |                       |
| 25                    | Command,                               | Unified command, perso<br>equipment working prop                             | onnel in place, clear resp<br>perly   | onsibilities,  |                                  |                       |
| 26                    | communi-<br>cation,<br>security        | Lifting action sound and   | light prompts work nor  | mally  |                                  |                       |
| 27                    | alert                                  | Have a security guardiar   | nship area and have a de  | dicated person   |                                  |                       |
| 28                    | Cable line<br>and<br>switch box        | It meets the calculation industry standard "Safet Construction Sites"; set   | requirements for line loa<br>cy Technical Specificatio<br>a special switch box. | ad in JG46 of the current<br>ns for Temporary Use of                       |                                  |                       |
|                       |  |  | Acceptance  |  |                                  |                       |
| Inspection conclusion | nspec-<br>on Rectifi-<br>onclu- cation |  |   |  |                                  |                       |
|                       |  |  |   |  |                                  |                       |
|                       | Inspector's<br>signature               | Main<br>contractor   | Client  | Special program editing production company                                 |                                  | onstruction<br>ompany |
|                       |  |  |   |  |                                  |                       |
|                       |  |  |   |  | Date                             | :                     |


### "GT-18 Self Climbing Platform Pre-Down Inspection and Acceptance Form"

| Р                  | roject   |   | Operational<br>type                       | hoist, decline    |  |  |  |
|--------------------|--|---|---|-------------------|--|--|--|
| Wo                 | rking layer  | Decline height (m)  | Decline grouping                          |                   |  |  |  |
| Mai                | in contractor  |   | Project manager                           |                   |  |  |  |
| Clie               | ent  |   | Project manager                           |                   |  |  |  |
| Spe<br>edi<br>tior | ecial program<br>ting produc-<br>n company                 |   | Project manager                           |                   |  |  |  |
|                    | nstruction<br>npany  |   | Project manager                           |                   |  |  |  |
| S/N                | Inspection<br>Item   | Inspection content  |   | Inspection result |  |  |  |
| 1                  | Concrete strength<br>at the attaching<br>support base jack | Reach the calculated value of the safety special construc   | tion plan, and ≥15MPa                     |                   |  |  |  |
| 2                  |  | Frame height≤5 times storey height, Frame width≤1.2n  | า   |                   |  |  |  |
| 3                  |  | The frame has no structural changes, missing componer   | ts, and damage.                           |                   |  |  |  |
| 4                  | Scaffolding condition                                      | The components of the frame are connected without mis connection is reliable.                                       | ssing and the                             |                   |  |  |  |
| 5                  |  | The unloading device at the vertical major frame shall no not use fastener or wire rope shall be used as the unload | ot be less than 2, and can<br>ing device. |                   |  |  |  |
| 6                  |  | The safety protection facilities are not damaged.   |   |                   |  |  |  |
| 7                  |  | attaching support base jack for each existing floor covere<br>the vertical major frame                              | ed by                                     |                   |  |  |  |
| 8                  | Attaching<br>support<br>base jack                          | The anti-drop, anti-roll and guide devices on the attachin support base jack are intact.                            | ng  |                   |  |  |  |
| 9                  | Dase Jack  | attaching support base jack adapt double nut to reinforc  | ed.                                       |                   |  |  |  |
| 10                 |  | The lifting device is set up at the vertical major frame  |   |                   |  |  |  |
| 11                 | Lifting  | Lifting support adapt double nut to reinforced.   |   |                   |  |  |  |
| 12                 | equipment  | equipment The connection of the lifting system components is not cracked, damaged, and the connection is firm.      |   |                   |  |  |  |
| 13                 |  | The lifting system is cleaned, maintained and runs smoo   | thly                                      |                   |  |  |  |



| S/N                   | Inspection items  |   | Inspection contents  |  |  | Inspection result |  |
|-----------------------|---|---|--|--|--|-------------------|--|
| 14                    | Lifting   | The power equipment c<br>relevant standards, and<br>the startup is sensitive, a | omplies with the instru<br>the suspension is corre<br>nd the operation is norr | ction manual and the cect, the connection is renal.                      | urrent<br>liable,                      |                   |  |
| 15                    | equip-<br>ment  | ly  |  |  |  |                   |  |
| 16                    |   | Each machine position is ment, and it can function                              | not less than one set of<br>in both use and lifting o                          | anti-overturning equip-<br>conditions.                                   | -                                      |                   |  |
| 17                    | Anti-over-  | Anti-overturning equipm   | ent completed, Working   | condition is normal  |  |                   |  |
| 18                    | turning<br>equipment  | After cleaning, inspection reliable.  | n and maintenance, it is   | easy to operate, sensitiv  | e and                                  |                   |  |
| 19                    |   | The installation position   | is correct and the stop is   | s effective.   |  |                   |  |
| 20                    | Anti-drop   | For lifting conditions, th<br>most guides is ≥ 2.8m,<br>distance between the up | e minimum distance bo<br>or ≥ 1/4 height; in the<br>permost and lowermost      | etween the uppermost<br>working condition, the<br>guides is ≥ 5.6m, Or ≥ | and lower-<br>e minimum<br>1/2 height. |                   |  |
| 21                    | device  | The cantilever height of t  | the frame is ≤ 2/5, and ≤  | ≤ 6m   |  |                   |  |
| 22                    | Obstacle, constraint  | Obstacles and restraints  | of unobstructed scaffold   | ling are lifted  |  |                   |  |
| 23                    | removal   | All the wall bars on the fr   | ame are removed  |  |  |                   |  |
| 24                    | Operators   | Hold a certificate and ha   | ve a Safety and Technol  | ogy Training record  |  |                   |  |
| 25                    | Command,  | Unified command, perso equipment working prop                                   | nnel in place, clear resp<br>erly  | onsibilities,  |  |                   |  |
| 26                    | communi-<br>cation,<br>security   | Lifting action sound and  | light prompts work norn  | mally  |  |                   |  |
| 27                    | alert   | Have a security guardian  | ship area and have a de  | dicated person   |  |                   |  |
| 28                    | Cable line<br>and switch<br>box   | It meets the calculation industry standard "Safe Construction Sites"; set a     | requirements for line l<br>ty Technical Specificat<br>a special switch box.    | oad in JG46 of the curr<br>ons for Temporary Use                         | rent<br>e of                           |                   |  |
|                       |   |   | Acceptanc  | e  |  |                   |  |
| Inspection conclusion | Rectifi-<br><sub>J-</sub> cation  | Rectifi-  |  |  |  |                   |  |
|                       |   |   |  |  |  |                   |  |
|                       | Main Special program Inspector's contractor editing production company  Client editing production company |   |  |  |  |                   |  |
|                       |   |   |  |  |  |                   |  |
|                       |   |   |  |  | Date:                                  |                   |  |

### 9.4 Pre-Tightening Electric Hoist Steps and Methods



### 9.5 GT-18 Self Climbing Platform Requirements

Implement the principle of "safety first, prevention first".

Construction personnel shall abide by the "Safety Technical Operation Regulations for Construction and Installation Workers".

#### Lifting operation safety measures:

A:To do not raise and lower with four principles: Rain, five grades (including five grades) above the strong wind, no rising and falling; When the sight is not good, no rising and falling; No lift inspection, no rising and falling; Division of labor, responsibility is not clear, no rising and falling.

B:The warning line shall be set on the ground during lifting operations, and any unrelated personnel shall not be in the warning line.

C:When the construction site is large, sufficient walkie-talkie should be configured to strengthen communication links.

D:No personnel shall stay on the climbing frame when the climbing frame is lifted or lowered.



### **Precautions for use**

1. After the GT-18 Self Climbing Platform is assembled in one time, it enters the structural construction stage. When using scaffolding at this stage, it must be used according to the construction plan requirements and the operation method of this manual. It is necessary to offer technology disclosure for each construction team.

2.All personnel are prohibited from being put on frame during the lifting operation of the scaffolding. After the lifting is completed, the climbing frame operator checks the frame and confirms that the "GT-18 Self Climbing Platform Lifting Checklist" and the "GT-18 Self Climbing Platform Falling Checklist" (Appendix A. After the requirements of 1.4 and Appendix A.1.5), Party A shall be notified to arrange for the construction of other construction workers.

3.After the scaffolding is set up according to the design plan, it is forbidden to carry out any expansion, erection and connection activities on the scaffolding. It is forbidden to hang advertising billboards on the external frame.

4.The materials is prohibited on the frame body, and each time the concrete is finished, Party A arranges personnel to clean up.

5. When the scaffolding is in use, no one can remove the scaffolding member at will. The components of the scaffolding must not be replaced by other materials.

6.Before the scaffolding is lifted, the owner of the main control box must be designated. The operator should not talk to people during the lifting process, and should not be away from the main control box within 10 meters.

7. Scaffolding prohibits the following illegal operations during use: lifting materials by scaffolding, strolling on scaffolding, lifting and hoisting cables on scaffolding, arbitrarily removing structural parts or loosening joints, removing or moving safety measures on scaffolding, tower cranes Do not collide or pull the scaffolding frame when lifting the material, and prohibit dumping construction waste on the scaffolding aisle.

8.In the event of typhoon weather, the frame should be reinforced according to the "Typhoon Emergency Plan".

9.During the use of scaffolding, it should be checked once a month. For specific measures, see "GT-18 Self Climbing Platform Monthly Checklist"; The bolted joints, lifting power equipment, anti-rolling and anti-drop device, electrical equipment, etc, in the process of maintenance, the specific measures can be found in the "Monthly Maintenance Table".



### 10.2/A.1.4 GT-18 Self Climbing Platform Lifting Checklist

| Project   | Project Name       |                | Building Height   |                                  | Buildin    | g Storeies  |         |
|-----------|--------------------|----------------|---|----------------------------------|------------|-------------|---------|
| Installat | Installation floor |                | Number of hoisting machines   |                                  | Numbe      | r of set-up |         |
| Contrac   | tor                |                |   | Project manag                    | er         |             |         |
| Use Co.   |                    |                |   | Project manag                    | er         |             |         |
| Special   | programming Co.    |                |   | Project manag                    | er         |             |         |
| Installat | ion Co.            |                |   | Project manag                    | er         |             |         |
| No.       | Inspection Item    |                |   | Content                          |            |             | Results |
| 1         |                    | Techi          | nical disclosure record   |                                  |            |             |         |
| 2         |                    | No m           | issing, changing or dam   | naged components                 |            |             |         |
| 3         |                    | No da          | No damage, obvious deformation, broken welding of the components                      |                                  |            |             |         |
| 4         |                    | No m           | No missing or loose connection bolts  |                                  |            |             |         |
| 5         | Frame<br>situation | The s          | The sundries and construction waste on the frame have been cleaned up.                |                                  |            |             |         |
| 6         |                    | The b          | The bolt with the building structure has been released or re-fixed                    |                                  |            |             |         |
| 7         |                    | The c<br>has b | constraint between the r<br>leen released or reinstal                                 | ail and the attaching sup<br>led | port base  | jack        |         |
| 8         |                    | The c          | The constraint affecting the lifting operation has been released                      |                                  |            |             |         |
| 9         |                    | Obsta          | acles that hinder lifting h   | nave been removed                |            |             |         |
| 10        |                    | The c<br>requi | concrete strength at the rements and ≥15MPa   | adhesion support meets           | the desig  | า           |         |
| 11        |                    | Attac          | Attachment support installation position deviation ≤ 15mm                             |                                  |            |             |         |
| 12        | Support            | The a          | The attachment support is securely mounted and fits tightly to the building structure |                                  |            |             |         |
| 13        |                    | The s<br>meet  | upport is fixed by twin t<br>the requirements.  | ie rod, and the nut and t        | he base pl | ate         |         |
| 14        |                    | Adhe<br>funct  | sion support should havion  | ve anti-drop and anti- to        | ppling     |             |         |

| No.         | Item                            |  |  | Content   |   |                         | Results    |
|-------------|---------------------------------|--|--|---|---|-------------------------|------------|
| 15          | Support                         |  | The anti-d<br>ment supp  | rop device should not be<br>oort as the lifting device  | placed on the same attac                                | :h-                     |            |
| 16          | anti-drog                       | <b>1</b>   | The gap be<br>be less tha                                      | etween the guiding device<br>in 5mm   | e and the guide rail shoul                              | d                       |            |
| 17          | and anti-<br>toppling           |  | The anti-d   | rop device is flexible, sens  | sitive, and effective.                                  |                         |            |
| 18          | Device                          |  | Under the and lower  | lifting condition, the distance of the distan | ance between the uppern<br>≥1/4 height                  | nost                    |            |
| 19          |                                 |  | The lifting<br>equipmen  | system is installed correc<br>t and lifting system are re   | tly and the power<br>liably connected.                  |                         |            |
| 20          |                                 |  | The equiport of rotation                                       | ment at the bottom is ser<br>is correct.  | sitive, reliable, and the di                            | irection                |            |
| 21          | Lifting<br>device ar<br>control | nd   | The contro   | ol cabinet is working prop  | erly and has full functions                             | S.                      |            |
| 22          | system                          |  | Set a dedi   | cated switch box  |   |                         |            |
| 23          |                                 |  | The distrib<br>Specificati                                     | oution line complies with<br>ons for Temporary Electr   | the requirements of "Safe<br>city Use at Construction S | ety Technical<br>Sites" |            |
| 24          |                                 |  | Command  | ers and operators are rea   | dy  |                         |            |
| 25          |                                 |  | Communic   | cation equipment is work  | ing properly  |                         |            |
| 26          | Safety                          |  | Set a warn   | ing line or precautionary   | measure.  |                         |            |
| 27          | Protectio                       | n  | Reliably cl  | osed around the top hole  | , set the fence   |                         |            |
| 28          |                                 |  | A protectiv  | e door opening to the flo   | or at the top step                                      |                         |            |
| 29          |                                 |  | The gap be   | etween the top platform a   | and the floor is ≤ 30mm                                 |                         |            |
| 30          |                                 |  | The differe  | ence between the top plat   | form and the floor is $\leq$ 0.                         | 3m                      |            |
|             |                                 |  |  | Meet the requirements,  | agree to use()  |                         |            |
| Conclusions | Improve-<br>ment<br>content     |  | After the improvement meets the requirements, agree to use ( ) |   |   |                         |            |
| Che<br>Sign | cker<br>ature                   | Contractor Use Co. Special program-<br>ming Co. Installation Co. |  |   |   | stallation Co.          |            |
|             |                                 |  |  |   |   | Day                     | Month Year |



## 10.2/A.1.5 Self-checking List For GT-18 Self Climbing Platform After The Falling

| Project   |                       | 1                 | Elevation  |   | Layer            |                    |                   |
|-----------|-----------------------|-------------------|--|---|------------------|--------------------|-------------------|
| Installed | stalled floor         |                   | Number of falling  |   | Number<br>machin | r of<br>e position |                   |
| General   | contractor            |                   |  | Project Manager                                   |                  |                    |                   |
| Use the   | unit                  |                   |  | Project Manager                                   |                  |                    |                   |
| Special   | programming unit      |                   |  | Project Manager                                   |                  |                    |                   |
| Installat | ion Unit              |                   |  | Project Manager                                   |                  |                    |                   |
| No.       | Inspection Item       |                   | In   | spection situation                                |                  |                    | Inspection result |
| 1         |                       | Have t            | echnical disclosure  | record.   |                  |                    |                   |
| 2         |                       | There             | are no missing, chai   | nging or damaged compo                            | onents.          |                    |                   |
| 3         |                       | No dar            | No damage, obvious deformation and open welding of components.             |   |                  |                    |                   |
| 4         | Frame                 | No mis            | No missing or loose for connection bolts                                   |   |                  |                    |                   |
| 5         | situation             | Debris            | Debris and construction waste on the frame have been cleared.              |   |                  |                    |                   |
| 6         |                       | The bo<br>buildir | The bolt has been removed or reattaching to the structure of the building. |   |                  |                    |                   |
| 7         |                       | The co<br>base ja | nstraint between th<br>ick has been remov                                  | ne guide rail and the attac<br>ed or re-installed | ching supp       | oort               |                   |
| 8         |                       | Constr            | aints affecting lift o <sub>l</sub>  | perations have been rem                           | oved             |                    |                   |
| 9         |                       | Obstac            | cles to the lifting hav  | ve been removed                                   |                  |                    |                   |
| 10        |                       | The str           | ength of the concre<br>ements and more th                                  | ete at the abutment meet<br>nan or equal to 15MPa | s the desi       | gn                 |                   |
| 11        |                       | The de            | viation of abutmen   | t position is less than or o                      | equal to 1       | 5mm                |                   |
| 12        | Attaching<br>abutment | The ab            | utment is installed  | firmly, which is close to t                       | he buildir       | ng structure       |                   |
| 13        | asament               | The ab<br>meet r  | outment is fixed by c<br>equirement.                                       | double tie rod, the nut an                        | d washer         | are all            |                   |
| 14        |                       | The ab<br>falling | outment shall have g<br>prevention   | guiding functions for cap                         | sized and        |                    |                   |

| No.                       | Item                                |     |   | Content  |  |                  | Results         |
|---------------------------|-------------------------------------|-----|---|--|--|------------------|-----------------|
| 15                        | Attaching abutment                  |     | The capsiz<br>abutment                      | ed prevention device is n<br>as the lifting device                     | ot mounted on the same                                   |                  |                 |
| 16                        | Device of                           |     | The cleara<br>less than 5                   | nce between guide devic<br>mm  | e and guide rail should be                               | Э                |                 |
| 17                        | capsized<br>and fallin<br>preventic |     | The capsiz                                  | ed prevention device is fl   | exible, sensitive and effec                              | ctive            |                 |
| 18                        | preventio                           | 711 | Under liftir<br>guides is m<br>with the fra | ng conditions, the space l<br>nore than or equal to 2.8r<br>ame height | petween the top and bott<br>m, or more than or equal     | om two<br>to 1/4 |                 |
| 19                        |                                     |     | Correct ins<br>between p                    | tallation of lifting system<br>ower equipment and lifti                | , reliable connection<br>ng system.                      |                  |                 |
| 20                        |                                     |     | Power equ<br>the right d                    | ipment starts sensitively,<br>irection                                 | operates reliably and rot                                | ates in          |                 |
| 21                        | Lifting dev                         |     | The contro                                  | ol cabinet works normally  | with complete functions                                  |                  |                 |
| 22                        | system                              |     | Set up spe                                  | cial switch box  |  |                  |                 |
| 23                        |                                     |     | Distributio<br>technical c                  | n lines shall comply with<br>code for temporary use of                 | the requirements of "safe<br>electricity on construction | ety<br>on site"  |                 |
| 24                        |                                     |     | Command                                     | and operational person   | nel are in place   |                  |                 |
| 25                        |                                     |     | The comm                                    | unication equipment is v   | vorking normally   |                  |                 |
| 26                        | Safety                              |     | To place a                                  | cordon or alert  |  |                  |                 |
| 27                        | Protection                          | n   |   |  | be closed reliably, and g                                |                  |                 |
| 28                        |                                     |     | To set up a<br>the floor la                 | protective door opening<br>dder  | to the floor in the top of                               |                  |                 |
| 29                        |                                     |     | or equal to                                 | 30mm   | orm and the floor is less t                              |                  |                 |
| 30                        |                                     |     | Height diff<br>than or eq                   | erence between the top f<br>ual to 0.3m                                | loor platform and the floo                               | or is less       |                 |
|                           |                                     |     | 1   | Meet the requirement and   | d agree to use()   |                  |                 |
| Inspec-<br>tion<br>result | The rectification content           |     |   | After the rectification i  | n accordance with the re                                 | quirements,      | agreed to use() |
| Inspec                    | Gen<br>Inspector sign               |     | l contractor                                | Use the unit   | Special program-<br>ming unit                            | Insta            | llation Unit    |
|                           |                                     |     |   |  |  | D                | ate:            |



### 10.9/GT-18 Integrated Attachment Lifting Scaffolding Month Checklist

| Pro | oject Name                              | Machine Number                        |        |
|-----|---|---------------------------------------|--------|
| Ch  | ecker                                   | check date                            |        |
| No. | Item                                    | 1                                     | Status |
| 1   | Main frame                              |                                       |        |
| 2   | Tie rod, nut and wire teeth             |                                       |        |
| 3   | The protective net is tightly closed an | nd the bottom flap is tightly closed. |        |
| 4   | Frame arm height position               |                                       |        |
| 5   | Return spring of the needle             |                                       |        |
| 6   | Anti-roll device splint                 |                                       |        |
| 7   | Attachment bearing (with or without     | deformation)                          |        |
| 8   | Lifting the hanger (with or without de  | eformation)                           |        |
| 9   | Reverse chain spring                    |                                       |        |
| 10  | Whether the fasteners and bolts are f   | fastened everywhere                   |        |
| 11  | Working status of each control box (s   | synchronized)                         |        |
| 12  | Line laying (fixed and in good conditi  | ion)                                  |        |
| 13  | Electric hoist (whether the hoist is da | amaged)                               |        |

### 10.9/Monthly maintenance schedule

| No. | ltem                 | Content  | Consequence |
|-----|----------------------|--|-------------|
| 1   | Electric hoist       | Apply butter to chains and pulleys                 |             |
| 2   | Jack                 | Apply butter to the jack                           |             |
| 3   | Tie rod              | Apply butter to the tie rod                        |             |
| 4   | Flap                 | Repair the flaps, close to the self-tapping screws |             |
| 5   | Bolt                 | Reinforced bolts that are not fastened             |             |
| 6   | Electrical equipment | Re-seal the damaged line with tight tape           |             |

We insist on providing customers with the highest cost-effective formwork and scaffolding solutions and services.

High Altitude Removal



### **High Altitude Removal**

### 11.1 Preparation Before Dismantling

- 1. Prepare the plan and submit it to the project department for review.
- 2. Prepare equipment for the removal of special spreaders, wire ropes, etc. for climbing frames
- 3. Check the bearing condition of the main stressed bolts such as the attaching support base jack.
- 4.Clean up the waste on the frame to ensure the safety of personnel during the removal process.
- 5.During the whole demolition construction process, a safety warning line shall be set on the ground. The warning range shall be 5 to 10 meters outside the area to be demolished, and should have a time schedule, e.g. some part in the morning, some part in the afternoon. And the tower crane lifting area shall be set up with special personnel to prevent non-workers from entering the demolition area. Be sure to be safe. 6.Do technology disclosure for the operator.

### 11.2 Dismantling Process



#### 11.3 Precautions

- 1.0 The professional team has similar demolition experience and is trained to be employed.
- 2.0 Conduct on-site field visits to accurately measure the demolition scope of the climbing frame.
- 3.0 The site of the dismantling team shall be disclosure on site, and the scope of demolition, construction sequence, and safety attention points shall be clearly defined to avoid cross-over operations.
- 4.0 It is strictly forbidden to drink, naked ,pay attention to the care products.
- 5.0 On-site command, supervision, operation, and warning are in place, and the requirements of the "Safety Technical Standard for Construction Tools and scaffolding" should be observed. The personnel should do:
- 5.1 Wearing belts and helmet, the spanner and straps to avoid falling.
- 5.2 Unified command, the demolition of the frame material is caught firmly, and it is strictly forbidden to throw.
- 5.3 A clear division of work, individual responsibility
- 6.0 Strictly follow the construction process:
- 6.1 Remove waste, garbage, and obstacles from the frame.
- 6.2 Thoroughly inspect the frame to ensure that the frame can be safely removed. The contents of the inspection are: the condition of each component of the frame, the force of each attachment and something like that.
- 6.3 It is strictly forbidden to carry out demolition work at 5 grade and above with strong winds or heavy rain, heavy snow, dense fog, thunderstorms and nighttime.
- 6.4 The demolition personnel must wear safety protective equipment correctly. The safety protection equipment must be connected to the building structure. It is forbidden to be attaching to the frame body. The safety officer is responsible for the on-site safety command work.
- 6.5 Dismantle from top to bottom, floor and area sequentially, it is forbidden to dismantle both top and bottom at the same time.
- 6.6 It is strictly forbidden to throw everything down during the whole process of dismantling the scaffolding.



## GT-18 Self Climbing Platform Installation and Common Use Tools

### List of Tools for Installation of GT-18 Self Climbing Platform

The number of tools listed in this table is based on 40 seats. The actual situation should be adjusted according to the current situation and the number of seats.

| S/N | Name of Tool                            | Specification and requirement | Unit | ΩТΥ |
|-----|---|-------------------------------|------|-----|
| 1   | Screw Jack                              | 3 tons                        | pcs  | 1   |
| 2   | Electric hand drill                     | 220V                          | set  | 1   |
| 3   | Stainless steel drill bit               | Diameter 40mm                 | pcs  | 10  |
| 4   | One open-ended and plum combined wrench | 22mm                          | pcs  | 5   |
| 5   | One hole-ended and plum combined wrench | 24mm                          | set  | 8   |
| 6   | Diamond hydraulic drill                 | 40mm drilling bit             | set  | 1   |
| 7   | Safety hat                              | GETO                          | pcs  | 10  |
| 8   | Tape measure                            | Meter                         | pcs  | 5   |
| 9   | Wire stripper                           | LA815138                      | set  | 2   |
| 10  | Utility knife                           | standard                      | set  | 3   |
| 11  | Insulating waterproof tape              | 25x500mm                      | roll | 20  |
| 12  | Vice                                    | FO-2603A                      | set  | 2   |
| 13  | High-altitude safety belt               | standard                      | pcs  | 10  |
| 14  | New workman electric wrench             | XL-80032                      | set  | 5   |



| S/N | Name of Tool                                | Specification and requirement  | Unit   | QТY                  |
|-----|---|--------------------------------|--------|----------------------|
| 15  | Sleeve                                      | 24*150                         | pcs    | 5                    |
| 16  | Sleeve                                      | 22*75                          | pcs    | 5                    |
| 17  | Sleeve                                      | 8mm                            | pcs    | 5                    |
| 18  | Sleeve                                      | 24*75                          | pcs    | 10                   |
| 19  | multimeter                                  | 3280-10F                       | pcs    | 1                    |
| 20  | Test pen                                    | MNT -111302<br>digital display | pcs    | 1                    |
| 21  | Long nose pliers                            | 8 inch                         | pair   | 3                    |
| 22  | Phillips screwdriver                        | 3*75                           | pair   | 3                    |
| 23  | Phillips screwdriver                        | 6*150                          | pair   | 3                    |
| 24  | Slot type screwdriver                       | 3*75                           | pair   | 3                    |
| 25  | Slot type screwdriver                       | 6*150                          | pair   | 3                    |
| 26  | Aviation scissors                           | standard                       | pair   | 3                    |
| 27  | Angle grinder                               | Standard specification         | set    | 1                    |
| 28  | Grinding sheet                              | Standard specification         | box    | 2                    |
| 29  | Cutting slice                               | Standard specification         | box    | 3                    |
| 30  | Manual chain hoist                          | 1.5Ton, 3m                     | pcs    | 1                    |
| 31  | Positive and negative ratchet sleeve wrench | 24mm                           | set    | 2                    |
| 32  | Hand painting                               | 5005                           | bottle | Configure as request |
| 33  | Hand painting                               | Signal blue                    | bottle | Configure as request |

| S/N | Name of Tool             | Specification and requirement  | Unit | QТΥ |
|-----|--------------------------|--|------|-----|
| 34  | Cable ties               | 5X400  |      |     |
| 35  | Electric chain hoist     | 3 tons   |      |     |
| 36  | Electric hoist gear      | Standard specification   |      |     |
| 37  | Electric hoist pulley    | Standard specification   |      |     |
| 38  | Тар                      | Standard specification   |      |     |
| 39  | wrench jaws              | Standard specification   |      |     |
| 40  | Tap drift holder         | Standard specification   |      |     |
| 41  | wrench jaws drift holder | Standard specification   |      |     |
| 42  | Scissors                 | 45-degree angle scissors multifunc-<br>tional electrical trough scissors<br>universal PVC scissors |      |     |
| 43  | Large wrench             | 50mm   |      | 6   |
| 44  | Large wrench             | One end 41mm and one end 46mm combined open-ended wrench   |      | 2   |



### 13.1 Advantages

### GT-18 Self Climbing Platform is a new type of self-developed intelligent scaffolding. It has a number of national patents. The technical features and advantages of the product are as follows:

- 1. Adopt new attached support system, make the frame more safe and reliable.
- 2.Standard design.
- 3. Precise control system.
- 4. Quick and convenient disassembly and lifting.
- 5. Environmental protection, energy saving, low carbon design concept.
- 6. The body of the climbing scaffold made of new quality steel.

### 13.2 Production Comparison

1.Lifting the pedestal---Safety and Reliable



**GETO Climbing Scaffolding** 



2.The lifting point is located outside the frame and does not affect the passage of personnel



GETO Climbing Scaffolding



#### 3. The passage is orderly, unimpeded and barrier-free



**GETO Climbing Scaffolding** 





#### 4.Turning plate sealed----Close fit with the structure without gaps







Others

#### 5. Control System---Intelligent automatic control system



GETO Climbing Scaffolding



Others

#### 6.Lower hanger---Special steel frame, safe and reliable



GETO Climbing Scaffolding



Other:



7.GETO GT-18 type self climbing paltform and the building structure adopt twin screw attachment connection, which is safer and more reliable than some peer self climbing platform that only use single screw attachment.






**GETO Climbing Scaffolding** 

Other

### 13.3 Personal Protective Equipment







### **Projects Reference**



Asteria, Melaka, Malaysia




Mesahill Phase 4, Nilai, Malaysia





Agile Embassy Garden,Kuala Lumpur,Malaysia



Tri-Zen Residential, South Asia



Office Building, Southeast Asia

